

The Hendricks County Surveyor's Office is looking to get quotes for a project in the Country Aires Estates Subdivision. I have included an aerial and below a scope of work.

1. Replace the outlet section of the concrete pipe with one, 15" concrete end section.
2. With the current concrete pipe being older, we may have to concrete collar the connection for a proper seal.
3. Construct a 4ft wide by 40ft in length rip rap swale from the new end section to the existing drainage swale.
4. Use geo-textile fabric and revetment rip rap for the constructed swale.
5. Once the job is completed, finish grade all the disturbed work areas with grass seed and straw.

I will be doing a walkthrough on 4/30/2025. at 11am. Please let me know if you will be attending. I Would like to have quotes returned to me by 4pm on 5/12/2025 to be opened at 5/13/2025 Drainage Board. This project will have a 15-day completion date from the time the approved quote is awarded. This will need to be completed when ground conditions are suitable. We will meet at 8738 Tracy Dr Clayton. Please let me know if you have any questions.

Blake Stephenson
Drainage Inspector
Hendricks County Surveyor's Office
Office 317-718-6101
Cell 317-766-4273
bstephenson@co.hendricks.in.us



12-1-26-61E-300-004

12-1-26-61E-351-003

12-1-26-61E-351-002

12-1-26-61E-351-001

12-1-26-61E-354-007

12-1-26-61E-354-006

12-1-26-61E-354-005

WATERSIDE CT

PARK SHORE

12-1-26-61E-352-010

12-1-26-61E-352-009

12-1-26-61E-352-008

12-1-26-61E-372-007

12-1-26-61E-372-006

WOODCREEK DR

HOLLARD A TODD

12-1-26-61E-374-004

12-1-26-61E-372-005