

The Hendricks County Surveyor's Office is looking to get quotes for a project in the Woodcreek Farms Subdivision. I have included an aerial and below a scope of work.

1. Remove 2-3 trees as needed on the west side of Woodcreek Dr on the south bank.
2. Dredge out the sandbars and pull back ditch bank to existing banks on the west side of the road culvert. Spoils will need to be hauled away.
3. On east side of Woodcreek Dr, north side of the ditch, pull back the ditch bank. Remove saplings on the south side of the ditch bank. Fill in erosion area on north bank to line the ditch back out to the existing ditch banks.
4. Place revetment rip rap and geotextile fabric on both the east and west side of the road culvert, approx. 30ft on both the north and south sides of the ditch banks.
5. Place plywood accordingly when tracking over the sidewalks.
6. Once the job is completed, finish grade all the disturbed work areas with grass seed and straw.

I will be doing a walkthrough on 4/30/2025. at 9am. Please let me know if you will be attending. I Would like to have quotes returned to me by 4pm on 5/12/2025 to be opened at 5/13/2025 Drainage Board. This project will have a 15-day completion date from the time the approved quote is awarded. This will need to be completed when ground conditions are suitable. We will meet at 7359 Park Shore Dr, Avon. Please let me know if you have any questions.

Blake Stephenson
Drainage Inspector
Hendricks County Surveyor's Office
Office 317-718-6101
Cell 317-766-4273
bstephenson@co.hendricks.in.us



12-1-26-61E-351-003

12-1-26-61E-300-004

12-1-26-61E-351-002

12-1-26-61E-351-001

12-1-26-61E-354-007

12-1-26-61E-354-006

12-1-26-61E-354-005

PARK SHORE

12-1-26-61E-352-010

12-1-26-61E-352-009

12-1-26-61E-352-008

12-1-26-61E-372-007

12-1-26-61E-372-006

WOODCREEK DR

HOLLARD A TODD

12-1-26-61E-374-004

12-1-26-61E-372-005