

MERCER PRECON

All, I have included an aerial .

The Hendricks County Surveyor's Office is looking to get quotes for the George Mercer project.

1. Starting at the north end of the job, clear trees, and brush 25' from center of pipe for approx. 558' of ditch on both sides flush with the ground. Stumps do not need dug out. Treat stumps with tordon.
2. Brush and small trees are to be chipped and spread within the easement.
3. The doghouse MH at the red X will need to have a bottom poured once reset.
4. The Higginbottom at the yellow X will need to be raised so it can be removed for inspection.
5. Contractor must come back to seed and straw disturbed areas.
6. We will meet at the red X. Gate access at NW corner of field off E 150 S.

The cost of stone and all materials will need to be included in the quote. All pipe to be bedded in stone and installed according to the manufacturer specifications and in accordance with the Hendricks County Storm Water Handbook. I will be doing a walkthrough on 1/21/26 at 10:00 am. You must notify me by end of day on 1/26/26 if you plan to attend. You must be present at the walk through to submit a quote. I Would like to have **SEALED QUOTES** returned to me by 4pm on 1/26/26 to be opened at Drainage Board. **This project will have a 30-day completion date from the time the lowest bidder is notified weather depending.**

