

Gailcrest Precon – REVISED 8/13/2025

**All,**

**Please see the changes from the walkthrough today at Gailcrest.**

The Hendricks County Surveyor's Office is looking to get quotes for a project in the Gailcrest Subdivision. I have included an aerial and below a scope of work.

1. Dredge 230ft of ditch flowline starting at the road culvert heading east to the bend in the ditch. All spoils will need to be hauled away.
2. On the south ditch bank on the east side of Kaymar Dr, Place 120ft of geotextile fabric and reventment rip rap from the ditch flowline to the top of the bank.
3. At the bend on the south bank of the ditch use some of the spoils in that area to fix the ditch bank and seed and straw mat that area.
4. On west side of Kaymar Dr, pull back 15ft long of the north and south ditch bank from the ditch flowline to the top of the bank.
5. Place geotextile fabric and revetment rip rap on the same 15ft of north and south ditch bank on the west side of the culvert.
6. Once the job is completed, finish grade all the disturbed work areas with grass seed and straw.

I will be doing a walkthrough on 8/13/25 at 1pm. Please let me know if you will be attending. I Would like to have quotes returned to me by 4pm on 8/25/2025 to be opened at the 8/26/2025 Drainage Board. This project will have a 30-day completion date from the time the approved quote is awarded. We will meet at 227 Kaymar Dr. Danville. Please let me know if you have any questions.

