

Clermont Lakes Precon

The Hendricks County Surveyor's Office is looking to get quotes for a project in the Clermont Lakes subdivision. I have included a job site aerial, a wetlands assessment completed by Burke Engineering and below a scope of work.

1. Mow/brush cut all the red highlighted area (approx..1600ft in length by 30ft in easement width.) shown in the attached aerial.
2. Cut all trees within the same 1600ft by 30ft area of open ditch flush with the ground and apply tordon chemical to all cut trees. **Do not remove any stumps during tree removal.**
3. All trees and overgrowth will be hauled away. **No dump trucks are to be in the wetlands area, and the wetlands are not to be dug out or destroyed**
4. Fix any damaged outlets and finish grade all of the disturbed work areas with grass seed and straw.

I will be doing a walkthrough on 10/8/2025 at 9am. Please let me know if you will be attending. I Would like to have sealed quotes returned to me by 10/27/2025 to be opened at the 10/28/2025 Drainage Board. This project will have a 30-day completion date from the time the lowest bidder is notified. We will meet at 4252 Raintree Rd. Please let me know if you have any questions.

