

BARNETT PHASE 2

All, I have included an aerial .

The Hendricks County Surveyor's Office is looking to get quotes for phase 2 of the Barnett ditch project which was approved through the Hendricks County Drainage Board as an ARP project.

1. Starting where phase 1 stops clear trees and brush 25' from top of bank for approx.. 2,679' of ditch on west side for the lower portion and both side for the upper portion.
2. Remove bottlenecks and sand bars from the ditch.
3. Burning of trees will need to be done in the field area of the ditch (someone must be present while burning).
4. Spread spoils along the top of bank within the easement in the field area.

The cost of stone and all materials will need to be included in the quote. All pipe to be bedded in stone and installed according to the manufacturer specifications and in accordance with the Hendricks County Storm Water Handbook. I will be doing a walkthrough on 10/28/25 Following phase 1. You must notify me if you plan to attend. You must be present at the walk through to submit a quote. I Would like to have **SEALED QUOTES** returned to me by 4pm on 11/10/25 to be opened at Drainage Board. This project will have a **30-day completion date (if the same contractor gets more than one phase the this time may stack)** from the time the lowest bidder is notified weather depending. Please make note on your bid that this is an ARP funded project.

