

ACRES OF DIAMONDS PRECON

The Hendricks County Surveyor's Office is looking to get quotes for a project in the Acres of Diamonds Subdivision. I have included an aerial and below a scope of work.

1. Remove a section of sidewalk and haul away. Once completed, pour the sidewalks back to their original form.
2. Tear out and haul away approx.. 290ft of 18" plastic pipe.
3. Replace the same 290ft with 18" perforated HDPE double wall pipe from the curb inlet to the existing structure.
4. Properly mortar the new pipe connections at both structures as applicable.
5. Install a tee and tie in any sump or perimeter drains that you may encounter.
6. Disconnect any gutter drains and daylight them at the edge of the easement.
- 5 Remove 5 stumps and haul away.
7. Once the job is completed, regrade all the disturbed work area back to its original condition and throw loose straw over the entire disturbed area. Considering the time of year, the contractor will come back in the spring of 2026 to finish grade, grass seed and double net straw mat the work area.

The cost of all stone and materials **should** be included in the quote. All pipe to be installed according to manufacturer specifications and in accordance with the Hendricks County Storm Water Handbook and technical standard. I will be doing a walkthrough on 11/13/2025. at 9am. Please let me know if you will be attending. I Would like to have quotes returned to me by 4pm on 11/24/2025 to be opened at 11/25/2025 Drainage Board. This project will have a 30-day completion date from the time the approved quote is awarded and as weather permits. We will meet at 1719 Michelle Manor Danville. Please let me know if you have any questions.

