

BATZ PHASE 2 PRECON

All, I have included an aerial .

The Hendricks County Surveyor's Office is looking to get quotes for phase 2 of the Batz ditch project which was approved through the Hendricks County Drainage Board as an ARP project.

1. Starting at the NE tree line of 10293N or 950E clear trees, brush and bushhog 25' from top of bank for approx.. 3,212' of ditch on both sides.
2. Install a temporary log bridge (to be removed once complete) crossing to access the north and east sides of the ditch.
3. Remove bottlenecks and sand bars from the ditch.
4. Burning of trees will need to be done in the field area east of the ditch, we will pile the areas in the woods within our easement. Someone must be on site at all times during burning.
5. Spread spoils along the top of bank within the easement in the field area.
6. Contractor must come back to seed and straw grassy areas in the spring. The areas must be rough graded and loose straw placed over any disturbed dirt areas for the winter.

The cost of stone and all materials will need to be included in the quote. All pipe to be bedded in stone and installed according to the manufacturer specifications and in accordance with the Hendricks County Storm Water Handbook. I will be doing a walkthrough on 11/17/25 at 10:00 am. You must be present at the walk through to submit a quote. You must let me know if you wish to attend. I Would like to have **SEALED QUOTES** returned to me by 4pm on 11/24/25 to be opened at Drainage Board. This project will have a 30-day completion date for phase 2 from the time the lowest bidder is notified weather depending. Please make note on your bid that this is an ARP funded project.

