

The Hendricks County Surveyor's Office is looking to get quotes in the Southern Ridge subdivision. I have included an aerial and below a scope of work.

1. Remove and haul away the tree/stump over the pipe.
2. Tear out approx.. 90ft of RCP from the pond past the manhole structure.
3. Tear out the pipe in the existing manhole.
4. Re-install approx.. 90ft of 12"RCP starting with the end section at the pond and past the manhole structure.
5. Seal/grout the new pipe in existing structure accordingly.
6. Install geotextile fabric and place rip rap around end section with animal guard.
7. Install stubs at manhole as applicable.
8. Once completed, re-grade the area around existing structure to the original grade.
9. Finish grade, fertilize, grass seed and straw mat all the disturbed work area.
10. One load of topsoil will likely be needed.

I will be doing a walkthrough on 4/25/2024. at 11am. Please let me know if you will be attending. I Would like to have **SEALED QUOTES** returned to me by 4pm on 5/13/2024 to be opened at 5/14/2024 Drainage Board. This project will have a 30-day completion date from the time the approved quote is awarded. We will meet at 7821 Hickory Ridge Ln. Please let me know if you have any questions.

Blake Stephenson
Drainage Inspector
Hendricks County Surveyor's Office
Office 317-718-6101
Cell 317-766-4273



06-3-23-41E-477-002

06-3-23-41E-477-003

06-3-23-41E-477-004

06-3-23-41E-477-001

Manhole

06-3-23-41E-477-016

06-3-23-41E-477-015

HICKORY RIDGE LN

SOUTHERN RIDGE DR

06-3-23-41E-478-002

06-3-23-41E-478-003